



Technical Facilities Hosting Services – Auxiliary Data Center (ADC)

Appendix D: Hardware Installation and Removal Considerations

- All hardware should be rack mountable and equipped with rails suitable for installing in 4 post racks. Third party rail kits are required to install Dell PE1950 and PE 2950 servers. Please contact Dell or Rack Solution (www.raksolutions.com). Please contact a Technical Facilities representative for additional information prior to ordering.
- All racks and cabinetry shall be seismically anchored. Non-standard hardware may require specialized methods of bracing beyond those listed above. This work will be performed using time and material rates.
- All removal activities require coordination and assistance by IT Services Technical Facilities.
- Due to University insurance requirements, combustible materials cannot be stored in the ADC.